

PEACE CORPS

Overseas Request for Quotation (RFQ) for Metal Works (metal doors, drop bar and window grills)

RFQ Number: 635-23-006

Date: 27- 04 April, 2023

Peace Corps Gambia has a need for a contractor to complete upgrade works at its new head office in Banjul. Peace Corps is soliciting fixed-price quotations from you and several of your competitors for the supplies and/or services detailed below.

If you are interested in submitting a quotation, please do so by sending your completed and signed Attachment 1—Vendor Quotation Form via e-mail to: gm-announcements@peacecorps.gov

Quotations are due no later than 5pm on Tuesday, April 04, 2023. Late quotations will not be considered.

Written questions about this Request for Quotation (RFQ) may be sent via e-mail address listed above in advance of the RFQ due date. No phone calls please.

Peace Corps will evaluate all quotations received by the deadline based on the minimum requirements and/or evaluation factor(s) shown below. Contingent on the availability of funds and continued need for the supplies and/or services, at the end of the evaluation process, Peace Corps intends to award a firm-fixed-price contract for the purchase of the required supplies and/or services to the selected vendor.

A. Statement of Work/Description of Requirements

	Description/Specification	Qty	Unit Price	Total
01	<p>Fabrication and installation of one drop down bar. The drop arm assembly is to be primarily made of strong steel.</p> <ul style="list-style-type: none"> •Ensure a smooth, oil painted (red & white) finish. •Ensure that the overall length of the drop bar is at least 7m. •The two end bars (60mm x 5mm) of 90cm height on both sides should be implanted into the ground, at a minimum of 1.5 meters deep. •In addition, a solid rope should be attached at the loose end of the drop arm, to allow the guards easily hold the anti-ram, when it needs to be opened. •The anti-ram barriers should be installed in a manner that it does not impede the entry of a vehicle 2.5 meters tall. 			
02	<p>Fabrication and installation of 03 Security Guard booth solid metal doors, 01 wide rolling gate (3m), and 8 (eight) other solid metal doors on the main office building, the new warehouse and the battery room per floor plan and design</p> <ul style="list-style-type: none"> • Convert existing metal gate into solid core doors • Provide all accessories including door closers • Paint with smooth black finish gloss paint • Install peephole on all the doors. 			
03	<p>Manufacture and install grilled doors as detailed below. Locally manufactured grills will be installed on all human-passable windows below 16 feet from the ground.</p>			

	16 X16mm square rods, The spacing should be maximum 120mm (we approximately 46 windows that may need to be grilled. Generator room to be meshed door and windows with at least 16 mm rebars. Prime and paint black			
Total				

B. Place of Performance

Site visit before submission: Wednesday March 29th, 2023, at 12 pm (Peace Corps Gambia New Office: Khamsys Technologies LTD, Bijilo, the Gambia)

C. Contract Terms and Conditions

As an Agency of the United States Government, Peace Corps has an approved contract template that it intends to use for the award. Peace Corps reserves the right to deny making a contract award to a vendor should they refuse to sign the Peace Corps approved contract template.

D. Minimum Criteria:

A quotation will not be considered further if it does not meet the following minimum criteria:

- It is complete and is received by the specified deadline.

E. Evaluation Factors:

Quotations that meet the minimum criteria listed above may be further evaluated based on the following factors:

- Price
- Delivery time
- Previous experience in similar projects – Please provide 03 references.
- Readiness to start as soon as possible.
- Capacity to Pre-Fund the entire construction work without asking PC for advance payment

Award may be made with or without negotiations between the Peace Corps and the selected vendor. Award may be made to a vendor that provided the lowest priced technically acceptable quotation, or to a vendor other than the one that provided the lowest priced quotation, should that vendor be determined to have provided the best value quotation to the Peace Corps taking technical and cost factors into account.

All vendors that submit quotations in response to this RFQ will be notified of the results.

[End of RFQ]

ATTACHMENT 1 – VENDOR QUOTATION FORM

RFQ Number: 635-23-005

Vendor:

Authorized Representative:

Name:

Position/Title:

Phone Number:

E-mail Address:

Quoted Prices (Inclusive of Administrative and/or Overhead Costs)

	Description/Specification	Qty	Unit Price	Total
01	<p>Fabrication and installation of one drop down bar. The drop arm assembly is to be primarily made of strong steel.</p> <ul style="list-style-type: none"> •Ensure a smooth, oil painted (red & white) finish. •Ensure that the overall length of the drop bar is at least 7m. •The two end bars (60mm x 5mm) of 90cm height on both sides should be implanted into the ground, at a minimum of 1.5 meters deep. •In addition, a solid rope should be attached at the loose end of the drop arm, to allow the guards easily hold the anti-ram, when it needs to be opened. •The anti-ram barriers should be installed in a manner that it does not impede the entry of a vehicle 2.5 meters tall. 			
02	<p>Fabrication and installation of 03 Security Guard booth solid metal doors, 01 big rolling gate (3 m), and 8 (eight) other solid metal doors on the main office building, the new warehouse and the battery room per floor plan and design</p> <ul style="list-style-type: none"> • Convert existing metal gate into solid core doors • Provide all accessories including door closers • Paint with smooth black finish gloss paint <ul style="list-style-type: none"> • Install peephole on all the doors. 			
03	<p>Manufacture and install grilled doors as detailed below Locally manufactured grills will be installed on all human-passable windows below 16 feet from the ground. 16 X16mm square rods, The spacing should be maximum 120mm (we approximately 46 windows that may need to be grilled. Generator room to be meshed door and windows with at least 16 mm rebars. Prime and paint black</p>			
	Total			

Items/Services Included in Total Quoted Price Above but Not Indicated in Chart:

Quoted Work or Delivery Schedule (If Any):

Quoted Payment Terms:

Quoted Warranty Terms (If Any):

Quoted Additional Terms and/or Conditions:

Describe your company's current staffing structure and describe in detail your company's plan for providing qualified individuals to fulfill this requirement and providing supervision of your staff members assigned to work at the Peace Corps.

SUPPLIER AUTHORIZED REPRESENTATIVE

Signature: _____

Date: _____